| No. | Items of work | Per | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a.p. | | |
| 5 | B. M. stone cutting figures with painting .. | No. | | 2 | |
| 6 | Grade stones including figuring and painting .. | ,, | | 15 | |
| 7 | Index stones .. .. .. | ,, | | 15 | |
| 8 | Gauge stones cutting figures and painting .. | ,, | | 1 | |
| 9 | Register No. and date stones .. .. | ,, | | 1 | |
| 10 | Cutting trenches and grips without hills .. | Grade | | 10 | |
| 11 | Clearing jungle and small plants rooting .. | ,, | | 10 | |
| | *Constructing Sluice at R. L. 46.00 at C.S. 5.* | | | | |
| 1 | Earth work cut opening Bund .. .. | C.yd. | | 53 | |
| 2 | Refitting after construction of Sluice .. .. | ,, | | 53 | |
| 3 | Concrete in Surki mortar .. .. .. | C.ft. | | 132 | |
| 4 | Burnt brick in surki mortar .. .. | ,, | | 374 | |
| 5 | Burnt Stone slabs 6" thick and fixed in mortar.. | S.ft. | | 195 | |
| 6 | Plastering with surki mortar .. .. | Sqr. | | 4.43 | |
| 7 | Providing plug and rod with locking arrangements .. .. .. | No. | | 1 | |
| 8 | Rough stone work .. .. .. | C.yd. | | $5\frac{1}{3}$ | |
| | *Constructing a waste weir R. L. 50.00 length 90 feet.* | | | | |
| 1 | Earthwork excavation and forming right wing | C.yd. | | 33 | |
| 2 | Stone jelly surki concrete .. .. .. | C.ft. | | 376 | |
| 3 | Burnt brick or Burnt stone in surki mortar .. | ,, | | 913 | |
| 4 | Burnt stone slabs .. .. .. | S.ft. | | 386 | |
| 5 | Plastering with surki mortar .. .. | Sqr. | | 9.36 | |
| 6 | Cement pointing .. .. .. .. | ,, | | 1.24 | |
| 7 | Rough stone work with jelly backing and wedging | C.yds. | | 88 | |
| 8 | Jelly backing .. .. .. .. | ,, | | 30 | |
| 9 | Draft, approach clearing and utilising the same to bund, etc. .. .. .. .. | L. S. | | | |

K. V. SRINIVASA MURTI,
*Executive Engineer.*

## MYSORE DIVISION.

*Abstract Notification, dated 6th July* 1934.

The attention of the public is invited to the detailed Notification of 7th July 1934, regarding the sale of an old P. W. D. Sub-Division Office Building at Hunsur, on 28th July 1934, published on pages 881-882 of Part VI of the *Mysore Gazette*, dated 12th July 1934.

---

*Notification, dated 20th July* 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 27th August 1934 for improving Sree Karivaradaraja Temple at Chamarajnagar, Mysore Disitrict. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M., to 5 P.M., on office days.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 160 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Sree Karivaradaraja Temple at Chamarajanagar" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final, and legally binding

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract Estimate for Improving Sree Karivaradaraja Temple on the Hill near Chamarajnagar.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| | *Main Building.* | | |
| 1 | Earth work foundation for buttress .. .. .. | C.yd. | 9 |
| 2 | Size stone in mortar front dressed .. .. .. | C.ft. | 486 |
| 3 | Cement Pointing .. .. .. .. .. | Sqr. | 3.06 |
| 4 | Repairing the Pillars sunk in the corners of the mantap with necessary under pinning, etc., and keeping retaining slabs in one level complete .. .. .. .. | Lump sum | |
| 5 | Dismantling the present brick wall damaged .. .. | C.ft. | 118 |
| 6 | Burnt brick in mortar for constructing the same .. .. | ,, | 118 |
| 7 | Chunam plaster .. .. .. .. .. | Sqr. | 2.1 |
| 8 | Removing the concrete over roof .. .. .. | C.ft. | 192 |
| 9 | Concreting the roof new jelly concrete with mortar .. | ,, | 192 |
| 10 | Cement plaster ½″ thick .. .. .. .. | Sqr. | 3.84 |
| 11 | Removing and resetting burnt stone slabs with dressed joints on 3″ concrete bed with cement pointing .. .. | ,, | 3.30 |
| 12 | Removing Damaged parapet .. .. .. .. | R.ft. | 70 |
| 13 | Repairing the leaks in Garbha-Ankanam .. .. | Lump sum | .. |
| 14 | Removing the present Verandah tiled-roof .. .. | do | |
| 15 | Excavating foundation of stone pillars .. .. .. | C.yd. | 10 |
| 16 | Chunam concrete .. .. .. .. .. | C.ft. | 64 |
| 17 | Burnt stone in mortar .. .. .. .. | ,, | 108 |
| 18 | Cut stone pillars, capitals, beams .. .. .. | ,, | 146 |
| 19 | Burnt stone slabs of 6″ dressed and fixed for the top .. | S.ft. | 168 |
| 20 | Chunam concrete for the top .. .. .. .. | ,, | 84 |
| 21 | Cement plaster ½″ thick .. .. .. .. | Sqr. | 1.68 |
| 22 | Ornamental parapet .. .. .. .. .. | R.ft. | 82 |
| 23 | Chunam concrete for flooring .. .. .. .. | C.ft. | 39 |
| 24 | Flooring with burnt stone slabs dressing .. .. .. | S. ft. | 156 |
| 25 | Cement pointing .. .. .. .. .. | Sqr. | 1.56 |
| 26 | Ornamental parapet with Karivaradarajaswamy Image in the middle on Muladwara with ordinary parapet on 3 sides .. | Lump sum | |
| 27 | Levelling the present compound wall fixing the old pot tiles in mortar over it .. .. .. .. | R.ft. | 350 |
| | *Kitchen.* | | |
| 1 | Plastering with chunam .. .. .. .. | Sqr. | 2.90 |
| 2 | Concrete flooring with smoothening and cement wash rendering | ,, | .54 |
| 3 | Constructing a Chimney .. .. .. .. | Lump sum | .. |
| 4 | White Washing .. .. .. .. .. | Sqr. | 42.00 |
| 5 | Pointing rough stone with mud .. .. .. .. | Lump sum | .. |

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| | *Anjaneyaswamy Temple.* | | |
| 1 | Removing the present shed | Lumpsum Rs. | .. |
| 2 | Earth work | Cyds. | 16 |
| 2 (a) | Concrete for foundation | C.ft. | 213 |
| 3 | Burnt Stone in mortar | ,, | 1054 |
| 4 | Burnt Stone slabs 6″ thick dressed and fixed | Sqr. ft. | 135 |
| 5 | Cut stone work pillars and capitals | C.ft. | 111 |
| 6 | Do (Cut stone beams) | ,, | 83 |
| 7 | Burnt stone slabs 6″ dressed and fixed on top | S.ft. | 226 |
| 8 | Chunam concrete for top with smoothening and ½″ thick cement plastering | C.ft. | 139 |
| 9 | Ornamental parapet in brick in chunam with 9″ cornice below and coping at top complete | R.ft. | 68 |
| 10 | Flooring with concrete with smoothening and cement-wash | Sqr. | 81 |
| 11 | Flooring with Cuaddapah slabs on 3″ concrete bed with cement pointing | ,, | 36 |
| 12 | Cement pointing | ,, | 9·14 |
| 13 | Teak wood 2″ thick battened door including cutting groves in slabs locking arrangements, etc. | S.ft. | 18 |
| 14 | Clearing and removing debris and unforeseen charges | Lumpsum | .. |

V. V. PATANKAR,
*Executive Engineer.*

## HASSAN DIVISION.

*Notification, dated 20th July* 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 13th August 1934 for Constructing a Local Fund Dispensary Building at Hole-Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a Local Fund Dispensary at Hole-Narsipur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12 Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.